

Tender Schedule for the work of Providing chip carpet to the existing WBM road at Coffee Board, TEC, Gonikoppa.

Sl.No.	Item No. & Page No.as per CPWD DSR.2007	Description	Unit	Approximate Quantity	Rate	Total in Rs.
1	16.30.1 / 243	Providing and applying tack coat using hot straight run bitumen of grade 80 / 100 including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications - On WBM @ 0.75 kg / sqm.	Sqm	4250.00	23.90	101575.00
2	16.33.1 / 244	2.5 cm premix carpet surfacing with 2.25 cum and 1.12 cum of stone chippings of 13.2 mm and 11.2 mm size respectively per 100 sqm and 52 kg and 56 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively including a tack coat with hot straight run bitumen including consolidation with road roller of 6 to 9 tonne capacity etc., complete (tack coat to be paid for separately) - With paving Asphalt 80 / 100 heated and then mixed with solvent at the rate of 70 grams per kg of asphalt.	Sqm	4250.00	100.35	426487.50
3	16.40 / 246	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen of grade 80 / 100 bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface including rolling and finishing with road roller all complete.	Sqm	4250.00	36.85	156612.50
4	19.6.5 / 316	Providing and laying non-pressure NP2 class(light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement: 2 fine sand) including testing of joints etc., complete - 450 mm dia R.C.C. pipe.	Metre	15.00	499.55	7493.25
5	6.2.2 / 99	Brick work with Modular bricks of class designation 75 in foundation and plinth in - Cement mortar 1:6 (1 cement: 6 fine sand).	Cum	2.00	2049.20	4098.40
6	13.1.2 / 201	12 mm cement plaster of mix - 1:6 (1 cement: 6 fine sand)	Sqm	25.00	67.65	1691.25
7	2.8.1/64	earth work excavation in foundation trench or drain etc as per item of 2.8.1/64 all kind of soil	cum	15	103	1545.00
Sub Total in Rs.						699502.90
Add cost index at (131 - 100 % 100) x 100 = 31%						216845.9
Total amount in Rs.						916348.80
Total amount rounded to in Rs.						9,16,350.00

Sd/-
ESTATE OFFICER
COFFEE BOARD, BANGALORE

I Abide by all the tender conditions enclosed with this schedule vide No. NO:Adm/Engg/GKP/Chip Carpet/2009/ 115 Dated: 15th June' 2009 and I am well aware of the same.

I agree to execute the above work at _____% (Percentage) ABOVE / BELOW.

EMD Particulars: i) Drawn on branch _____
ii). Demand Draft No. _____
iii). Amount in Rs. _____

TENDERER