

**Tender Schedule for providing and applying water proof compound on sloped RCC roof quarters at CCRI, Balehonnur, Chikmagalore District**

Sl. No.	CPWD DSR 2007 Item No. & Page No.	Description of Items	Unit	Approx. Quantity	Rate in Rs.	Amount in Rs.
1	15.23.1 / 228	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead - For thickness of tiles 10 mm to 25 mm	Sqm	800.00	10.90	8720.00
2	13.3.1 / 201	20 mm cement plaster of mix - 1:4 (1 cement: 4 coarse sand) (if required during the execution of work).	Sqm	848.00	110.45	93661.60
3	NS	Providing and applying two coats of elastometric cementitious water proofing compound over the prepared clean surface. The application shall be got done by an authorised applicator of the manufacturer of compound as per the standards laid out in ASTM-D-4541, ASTM-C-836.If requied points are to be selected for drilling hole of 20mm dia for the nozzle to be grouted with fast settling non shrinking chemical.	Sqm	975.00	280.00	273000.00
<b>Sub Total in Rs.</b>						<b>375381.60</b>
<b>Add cost index @ 6%</b>						<b>22522.86</b>
<b>Total in Rs.</b>						<b>397904.46</b>
<b>Total amount rounded to in Rs.</b>						<b>3,97,904.00</b>
					Sd/-	
					<b>ESTATE OFFICER</b>	
					<b>COFFEE BOARD</b>	
<b>I/We abide by the terms and conditions enclosed to the tender notification</b>						
I/We under take the work at tender percentage of-----above/below the amount put to tender.						
EMD particulars						
TENDERER						